

Vermont Department of Environmental Conservation

Agency of Natural Resources

Watershed Management Division

Barre Regional Office 5 Perry Street, Suite 80 Barre, VT 05641

802-476-0190 [phone] [fax] 802-476-0131


[cell]

802-279-1143

www.watershedmanagement.vt.gov **AUTHORIZATION TO CONDUCT NEXT FLOOD MEASURES**

Pursuant to Section F of the Vermont Stream Alteration General Permit

Tursdant to section to the vermont stream the deficition deficition deficition
Project Number: SA-3- <u>145</u> -2015
Applicant Name: Town or Derby GBOB KELLEY Phone: (602) 766-2017 Mailing Address: 124 MAIN STREET DERBY, VT 05829
Mailing Address: 124 MAIN STREET DERBY, VT 05829
Project Location: PINTE HILL ROBIS
Email: DERBYZA@DBEBYVT, ORG
The Secretary of the Vermont Agency of Natural Resources (VT ANR) has determined that: 1. This project authorizes stabilization of a failed culvert. Culvert is a public
safety concern. This repair will buy the town some time to do a full replacement the xt construction season (2016). The proposed activity is eligible for coverage under the VT ANR Stream Alteration General Permit - Next Flood Measures.
3. The proposed activity will meet the terms and conditions of Section F of the General Permit provided:
a) The project will be completed and approved as shown on the plan dated 11 2015, prepared
by Boes Kerrey and approved by the Vermont Agency of Natural Resources.
b) The project is proportional to the threat and conditioned to cease when the threat to life or to improved propert has ended.
c) The project will not result in a threat to life, public health or safety.
d) The project will meet the standards detailed in subsection E.2.1 and E.2.2 of the General Permit.
e) The project will meet Stream Alteration Standards to the greatest extent possible.
f) A pre-construction meeting is held between the contractor, owner/applicant, and the ANR River Management Engineer.
g) The River Management Engineer is notified by phone or email when construction begins and when the project is complete.
h) A final construction inspection is required for any culvert and bridge related work.
i) Additional conditions:
If there are any changes in the project plan or deviation in construction from the plan, the Permittee must notify the River Management Engineer immediately.
If the project is constructed as you have described, as shown on the above referenced approved plans and according to the above conditions, there is no reason to expect any violation of Vermont Water Quality Standards.
David K. Mears, Commissioner Department of Environmental Conservation
by: Patrick Poss R. F. River Management Engineer
Patrick Ross, P.E., River Management Engineer




L SINK HOLE DUE TO PIPENG OF MATERIALS.

INVERT OF CULVERT IS GONE DUE TO

ABRASION & RUST.

TRIMPORARY REPAIR - LINE INVERT WITH CONCRETE 6" THICK.

FULL REPLACEMENT - SUMMER 2016.



Havert in COMPLETELY GONE DUE TO 10 ft diameter culvert Concrete fill bottom of culvert where perforated RUST & DRICKS IS. BMPORANY 8" Avg Concete depth in pipe ガノコ アカヤンスとのスカメント PERRIC Summer 2016

G