

Vermont Department of Environmental Conservation

Watershed Management Division, Rivers Program

One National Life Drive – Main 2 Montpelier, VT 05620-3522 http://dec.vermont.gov/watershed Agency of Natural Resources

[cell] 802-345-3510 [fax] 802-828-1544 [phone] 802-828-1535

AUTHORIZATION TO CONDUCT STREAM ALTERATION ACTIVITIES

Pursuant to Section C.2.2.4 of the VT Stream Alteration General Permit

Project Number: SA-09-021-2016 Marlboro Higley Hill Road Culvert Extension

Applicant Name: Town of Marlboro Highway Department

Mailing Address: Town of Marlboro, PO Box 154, Marlboro, VT 05344

Project Location: Higley Hill Road TH 2 Culvert 2 on Bellows Brook

Email: marlborotreasurer@gmail.com

The Secretary of the Vermont Agency of Natural Resources (VT ANR) has determined that:

- 1. This project authorizes an 18' extension of an existing 10' span x 6' rise open bottom plate arch pipe on 4' tall concrete abutments with minor ledge removal and rip-rap bank stabilization for road surface improvements.
- 2. The proposed activity is eligible for coverage under the VT ANR Stream Alteration General Permit.
- 3. The proposed activity will meet the terms and conditions of the General Permit provided:
 - a) The project will be completed and approved as shown on the plans dated 11/2/16, prepared by Daniels Construction, and approved by the Vermont Agency of Natural Resources as herein.
 - b) The project will not adversely affect the public safety by increasing flood hazards.
 - c) The project will not significantly damage fish life or wildlife.
 - d) The project will not significantly damage the rights of riparian owners.
 - e) The project will not obstruct the movement of aquatic life indigenous to the waterbody beyond the actual duration of construction.
 - f) The project is conducted in a manner which minimizes or avoids any discharge of sediment or other pollutants to surface waters in violation of the VT Water Quality Standards.
 - g) The ANR River Management Engineer is notified by phone or email when construction begins and when the project is complete.
 - h) In-stream working dates for all GP activities are from July 1st through October 1st; any in-stream work outside these dates will require an Individual Stream Alteration Permit authorization by the River Management Engineer.
 - i) This authorization has been posted for three days public comment. This authorization constitutes final approval.

If there are any changes in the project plan or deviation in construction from the plan, the Permittee must notify the River Management Engineer immediately.

If the project is constructed as you have described, as shown on the above referenced approved plans and according to the above conditions, there is no reason to expect any violation of Vermont Water Quality Standards.

Signed this 1st day of December, 2016

David K. Mears, Commissioner

Department of Environmental Conservation

This permit expires October 1, 2017.

by IN Smun







DANIELS CONSTRUCTION P.O. Box 246 - 4409 Route 5

P.O. Box 246 - 4409 Route 5 Ascutney, VT 05030-0246 Phone: (802) 674-6323 Fax: (802) 674-5346

JOB Culvert Extension	JOB NO
DESCRIPTION Higler Hill Rd.	SHEET NOOF3
DESCRIPTION Higley Hill Rd. SUBJECT Marlbors, VT	SCALE N.T.S.
CALC. BY M. Belden	DATE 11/2/16
CHCK. BY	DATE


A N	
Bellows Brook (Town Highway 2)	
Existing Stone Leadwall in headwall	
good condition in failure Proposed 18 long	
Existing 10'span × 6'rise pipe arch structure bottomless pipe arch on	
4' tall concrete abutments	
Proposed Concrete Channel	18
headwall & wing - Bellows Bellows	\
Brook	
Stone Fill. Type II	
To VT Route 9 Plan Details * No clearing	



DANIELSCONSTRUCTION

P.O. Box 246 - 4409 Route 5 Ascutney, VT 05030-0246 Phone: (802) 674-6323 Fax: (802) 674-5346

JOB Colvert Extension	JOB NO
DESCRIPTION Higley Hill Rd.	SHEET NO 2 OF 3
DESCRIPTION Higley Hill Rd. SUBJECT Mariboro, VT	SCALE N.T.S.
CALC. BY M. Belden	DATE 11/2/16
CHCK BY	DATE






JOB CU	luert Extension
DESCRIPTION	Higley Hill Rd.
SUBJECT	Marlboro, VT
CALC. BY	M. Belden
CHCK. BY	

JOB NO				_
SHEET NO	3	_OF_	3	
SCALE	N:	T.S.		
DATE	11/2	16		
DATE				

Hig	ley	Hill	Rd.
-			



Section B-B

Project Overview	Approx. Duration
	1 day
Mobilize	1 day
Install traffic control devices (signs)	½ day
Install erosion control measures (silt fence, silt sock, hay bales)	2 days
Construct access ramp to brook	½ day
Divert Bellows Brook to center of channel utilizing sandbags	5 days
Construct concrete abutments for pipe arch	½ day
Divert Bellows Brook to one side using sandbags	½ day
Hammer high spots of ledge to channelize flow	½ day
Remove water diversion	2 days
Install pipe arch	10 days
Construct concrete headwall and wingwalls	2½ days
Backfill structure	½ day
Place stone fill	2 days
Construct stone-lined ditch and restore site	Z day.
Total Project Duration	28½ days
Total 'In-Stream' Project Duration	7½ days